Chiller restart after trip

FICTIONAL TRAINING DOCUMENT - NOT AN OPERATING INSTRUCTION

Document status: Reviewed seed revision Site: Hall 2 Permit: DEMO-026

Prerequisites / sign-off

Qualified technician, current work permit, local indications and chief engineer approval.

Read-back required before each step. Guardian advice never operates plant equipment.

One-line context (simplified; verify actual field labels)

Margin note: confirm flow and restart temperature limits before requesting a restart.

STEP	ACTION / VERIFICATION
1	Confirm voltage stabilized and notify chief engineer Verify: Verify local indication and record read-back.
2	Verify chilled water supply remains below restart limit of 62-F Verify: Verify local indication and record read-back. **Gate: temperature_below_62**
3	Request authorized operator restart; verify plant locally Verify: Verify local indication and record read-back.